

15-163-03020-02-02

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION ~~GSW No~~ CSEW

Lost hole - Halliburton Wire
in hole. On Cementing job.
Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well 17 W

I have today completed supervision of plugging of:

Well No. 1 Lease Russ "A"

Operator Herndon Drg Co Address Lyons, Kans

Field Dopita County Rooks

Total Depth 3420' Feet.

(Describe briefly the manner in which the well was plugged)

10 5/4" at 157' circulated with cement . 5 1/2" at 3417' . with
200 sax cement behind.

Cement up in pipe. They went in with cable tools to fish for
Halliburton line and lost tools (Hung up) at 2755')

Shot off 5 1/4" pulled and mudded hole to 157', set wood plug and
20 sax cement - Heavy mud to 25' wood plug, rock and 10 sax cement.

FL

PLUGGING
FILE SEC 31 T 8 R 17W
BOOK PAGE 111 LINE 24

District Conservation Agent

Date 8-22-49 AUG 29 1949

8/29/49

STATE CORPORATION
COMMISSION
KANSAS