

15-163-03723-00-20

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1968
CONSERVATION DIVISION
Wichita, Kansas
5/27/68

Operator's Full Name Fender Pipe & Supply, Inc.,

Complete Address: Box 302 Russell, Kansas

Lease Name Russ Well No. 1

Location SW NW Sec. 31 Twp. 8 Rge. 17 (E) (W) X

County Rooks Total Depth 3420'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Constr.

Address: Box 342 Eldorado, Kansas License No. 547

Operation Completed: Hour 4:30 P Day 16 Month 5 Year 1968

The Above well was plugged as follows:

Total Depth 3420' 10 3/4 csg set at 1300' cwc.

7" csg set at 3242' cw 75 sc cement.

5 1/2 csg set at 3420' cw 50 sc cement.

5 1/2 csg squeezed at 3246' W/85 sc cement.

5 1/2 csg PBTD 3362 with lane wells plug and 7 sc cement. Top perf. 3311'.

Filled 5 1/2 csg with sand to 3300' and dumped 5 sc cement with dump bailer. (3260-3300)

Ripped 5 1/2 csg at 1500' and recovered same.

Ripped 7" csg at 1500' and recovered same.

Pumped down 10 3/4 csg W/40 sc gel W/10 sc hulls, 200 sc 50-50 poz cem. W/4% add. gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 5/27/68
INV. NO. 17806-W