

15-065-30154-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1967
6-12-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Aspen Drilling Company.

Complete Address: Box # 783, Great Bend, Kansas.

Lease Name Manauh Well No. A-1

Location CSW-SW Sec. 29 Twp. 9 Rge. (E) (W)22

County Graham Total Depth 3852

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Incorporated.

Address: Box # 364, Great Bend, Kansas. License No. 496

Operation Completed: Hour 1:00PM Day 7 Month 6 Year 1967

The Above well was plugged as follows:

206'--8 5/8" Surface pipe, cement circulated with 200 Sx.

3851'--5 1/2" Production casing cemented with 120 Sx. Top perforations from 3777' to 3782'.

Sanded well back to 3750' and set 5 Sx. cement with dump bailer.

~~SM~~ Pulled 5 1/2" casing and squeezed hole with 20 Sx. gel using 5 sacks hulls in initial gel and followed with 75 Sx. cement. Maximum pump-in pressure 600#, final shut-in pressure 125#. (Recovered 3020' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 6/12/67
INV. NO. 5367-u