

15-163-03019-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CNE $\frac{1}{4}$  SW $\frac{1}{4}$

SEC. 31 TWP. 8 RGE. 17

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Dopita

Operator Harbar Drg Co Address Great Bend

Field Dopita County Rooks

Total Depth 5424 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 135', circulated with cement - 5 1/2" at 5410'

Lane Wells plugs to 5381', top perforations at 5140'.

Chat 5381 to 5140' and 5 sax cement - Heavy mud to 135',

wood plug, rock and 15 sax cement - Heavy mud to 50', wood

plug, rock and 10 sax cement.

Pulled 2805' 5 1/2".

**PLUGGING**  
SEC. 31 T. 8 R. 17  
FILE 105 19

*[Signature]*  
District Conservation Agent  
**RECEIVED**

Date 7-11-49 Conservation Div.

7/14/49 JUL 14 1949  
STATE CORPORATION  
COMMISSION  
KANSAS