

RECEIVED
STATE CORPORATION COMMISSION
KANSAS
OCT 07 1982
CONSERVATION DIVISION AGENT REPORT
Wichita, Kansas

FORM CP-3
Rev. 1-8-82

API Number 15-163-21,813 0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name GENE BROWN

Complete Address 407 SOUTH MAIN, PLAINVILLE, KANS. 67663

Lease Name RUSS Well No. #1-A" (SWD)

Location 75' FEL - 890' F.S.L. Sec. 31 Twp. 8 Rge. 17 (East)(West)

County ROCK Total Depth 1627 FE.

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☒ D&A ☐

Other well as hereinafter indicated LOST CIRCULATION - ABANDONED AND PLUGGED

Plugging Contractor HELBURG OIL COMPANY. (JOHN WETS)

Address BOX 32 MORLAND KANS. 67650 License No.

Operation Completed: Hour: 9:45 AM Day: 1st Month: OCT Year: 19 82

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

The above well was plugged as follows:

LOST CIRCULATION @ 1627. - ABANDONED AND PLUGGED (REPORT ATTACHED)
ORDERED 310 \pm 50/50 FORMIX 4% GEL - 3% CA-CL AND 8 5/8" PLUG.
8 5/8" 179 FE SP. CUC BY HALLIBURTON CEMENTING.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 1380 FE w/ 100 \pm CMT.

2nd Plug @ 1210 FE w/ 50 \pm CMT.

3rd Plug @ 660 FE w/ 100 \pm CMT.

4th Plug @ 270 FE w/ 40 \pm CMT.

5th Plug (SOLID BRIDGE @ 40 FE to 0 w/ 10 \pm CMT. (10 \pm IN PAYABLE) (CIRCUMFERENCE)

Amount of Surface Casing: 179 FE (CEMENTED BY HALLIBURTON)

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-18-82

INV. NO. 1378-W