

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1976
02-17-1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20599-00-00

Operator's Full Name Cities Service Oil Co.

Complete Address 209 E. William, 700 Sutton Place Bldg., Wichita, Kansas

Lease Name Kriley "B" Well No. 1

Location SW SW SW Sec. 15 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3425'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 9:15 A Day 16 Month 2 Year 1976

The above well was plugged as follows:

RTD 3425' 8 5/8 csg set 208' cwc 175 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 2-25-76

NV. NO. 2790-W