

15-163-20614-00-02 R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1976
APR 26 1976
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 163 - 20,614 - 00 - 02 (of this well)

Operator's Full Name Murfin Drlg. Co.
Complete Address 617 Union Center, Wichita, Kansas
Lease Name Richard "D" Well No. 1
Location 1320' FSL & 990' FWL of NE/4 Sec. 23 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3431'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 2:15 P Day 25 Month 4 Year 1976

The above well was plugged as follows:

RTD 3431' 8 5/8 csg set 183' cwc 135 sk. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 535' thru drill pipe.
Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messery
Well Plugging Supervisor

DATE 4/30/76
INV. NO. 3132-W