

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1974
CONSERVATION DIVISION
Wichita, Kansas
7-16-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-63-20535-00-00

Operator's Full Name Cities Service Oil Co.
Complete Address 209 E. William, 700 Sutton Place, Wichita, Kansas
Lease Name Mosher Well No. 5
Location NE SE SE Sec. 21 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3465'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drlg.
Address Wichita, Ks. License No.
Operation Completed: Hour 7:30 P Day 13 Month 7 Year 1974

The above well was plugged as follows:

RTD 3465' 8 5/8 csg set at 219' cwc 175 sk.
Gunned pits, circulated heavy mud, set cementing plug at 675' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 245' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Red F. Massey
Well Plugging Supervisor

INVOICED

DATE 7/16/74
INV. NO. 9541-W