

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20603-00-00

MAR 01 1976
3-1-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cibies Service Oil Co.

Complete Address 209 E. William, 700 Sutton Place Bldg., Wichita, Kansas

Lease Name Hrabe "A" Well No. 3

Location C N/2 SE NE Sec. 21 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3471'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 11:15 P Day 26 Month 2 Year 1976

The above well was plugged as follows:

RTD 3471' 8 5/8 csg set 228' cwc 175 sk. Plg. Mat. 50-50 poz. 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 250' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-2-76

INV. NO. 2831-6