

J
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-163-20082-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 15 1967
12-15-67
CONSERVATION DIVISION
1963

Operator's Full Name Cameron K. Reed
Complete Address: 20 West Ninth St. Kansas City, Missouri
Lease Name Swanson Well No. 1
Location NW NE SW Sec. 17 Twp. 8 Rge. 18 (E) (W) X
County Rooks Total Depth 3480'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Gabbert-Jones
Address: Wichita, Kansas License No.
Operation Completed: Hour 3:15 A Day 12 13 Month --12-- Year 1967

The Above well was plugged as follows:
RTD 3480' 8 5/8 csg set at 200' cwc 165 sc.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Pluggedrat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/15/67
INV. NO. 6915-4

Signed: Geo F. Mussey
Well Plugging Supervisor