

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20433-00.00

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 - 1972

S-1-72

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Oil Company

Complete Address 200 W. Douglas Suite 550 Wichita, Kansas

Lease Name Meshor Well No. 3

Location NE SW SE Sec. 21 Twp. 8 Rge. (E) (W) 18

County Reeks Total Depth 3450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 11 A Day 29 Month 4 Year 1972

The above well was plugged as follows:

RTD 3450' 8 5/8 set at 214' cwc. Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. Murray
Well Plugging Supervisor

DATE 5-3-72
INV. NO. 5671-W