



15-143-20431-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

4/27/72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Davis of Heller Drlg. has this

date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: F & M Oil Co.

Complete Address: 603 Union Center Bldg., Wichita, Ks.

Lease Name: Cerrow Well No. 1

Location: SE NE SW Sec. 34 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3473' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Davis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo P. Manser  
Conservation Division Agent