



15-163-20156-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. - 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
11-27-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Harre of Broken Arrow Drlg. has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: Natl. Ass. Petr. Co.

Complete Address: Fourth Floor Petroleum Bldg., Tulsa, Okla.

Lease Name: Thibault-Brin Comm Well No. 1

Location: G S/2 SE NW Sec. 30 Twp. 8 Rge. 20 (E)(W) X

County: Rooks Total Depth 3798' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Harre was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace 70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

[Signature]  
Conservation Division Agent