

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Victor Justus of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Justus guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company,

Complete Address: 520 Cameron Building, Oklahoma City, Oklahoma.

Lease Name: Leck Well No. 1

Location: SW-NE-NE Sec. 8 Twp. 8 Rge. (E)(W) 21

County: Graham Total Depth 3590' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Justus was instructed to plug the well as follows:

321'---8 5/8" Surface casing, cement circulated with 230 Sx.  
Mr. Errol Conn, Land Owner, has requested well be left open in surface pipe to be used as a potential fresh water well. Signed Authorization to accompany Plugging Report.

Circulate hole with heavy mud. Pull DP to 690' and displace 130 Sx. cement from 690'. Pull DP to 300' and circulate clear water to surface to facilitate conversion to fresh water well.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 14 1968 OCT 14, 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

W. L. Deibel  
Conservation Division Agent