



15-065-20225-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAY 26 1969

CONSERVATION DIVISION  
Wichita, Kansas

5-26-69

Dear Sir:

Mr. Eldon Reed of Aspen Drilling Company, has this date requested permission to plug the following described well:

Mr. Reed guarantees payment of the plugging fee.

Operator's full Name: Robert R. Price and Aspen Drilling Company,

Complete Address: P. O. Box #783, Great Bend, Kansas.

Lease Name: Kansas Childrens Home Well No. 1

Location: NE-SW-NE Sec. 16 Twp. 8 Rge. (E)(W) 21

County: Graham Total Depth 3545' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Reed was instructed to plug the well as follows:

237'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 525'.

Circulate hole with heavy mud. Pull DP to 750' and displace 100 Sx.  
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull DP,  
set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*N. L. Dehals*  
 Conservation Division Agent