



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

15-163-21200-00-00

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Harold Maley of Abercrombie Polg. Co. ⁽²¹⁹⁷⁾ has this date requested permission to plug the following described well:

Operator's Full Name: F. + M. Oil Company Inc.

Complete Address: 422 Union Ctr. Wichita, Kans

Lease Name: Hriley Well No. #1

Location: SE-NW-SW Sec. 15 Twp. 8^S Rge. 18^W (E) (W)

County: Rooks Total Depth: 3350^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Maley was instructed to plug the well as follows:

- 8 5/8" 249^{FE} SQ. CUC w/ 190ST Cement - 2% Gel - 3% Co. Cl.
- Order 110ST 50/50 Pozmix 6% Gel + 8 5/8" Plug (E.V. 1898 H.B.)
- Spot with Drill Stem - With Heavy Mud Between all Plugs.
- 1ST Plug @ 740^{FE} w/ 70ST Cmt.
- 2ND Plug @ 240^{FE} w/ 25ST Cmt.
- 3RD Plug - Solid Budge - Nulls - Plug @ 40^{FE} 70ST w/ 10ST Cmt.
- 5TH A. Cat Hole

Very truly yours, (By Sam Smith)

Samuel J. Schmidt
Conservation Division Agent

NOV 24 1980
12-24-1980
CONSERVATION DIVISION
Wichita, Kansas