

State of Kansas



15-163-20082-00-00

ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

DEC 15 1967
 12-15-67
 CONSERVATION DIVISION

Dear Sir:

Mr. Johnson of Gabbert-Jones has this

date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Cameron K. Reed

Complete Address: 20 W. 9th St. Kansas City, Missouri

Lease Name: Swanson Well No. 1

Location: NW NE SW Sec. 17 Twp. 8 Rge. 18 (E)(W) X

County: Rooks Total Depth 3480 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Messy
 Conservation Division Agent