



15-163-20433-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 1 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
5-1-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lehar of B & B Drlg. has this  
date requested permission to plug the following described well:

Mr. Lehar guarantees payment of the plugging fee.

Operator's full Name: National Oil Company

Complete Address: 200 W. Douglas Suite 550 Wichita, Kansas

Lease Name: Mosher Well No. 3

Location: NE SW SE Sec. 21 Twp. 8 Rge. (E)(W) 18

County: Reeks Total Depth 3450' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Lehar was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 550' and displace  
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Manning  
Conservation Division Agent