



15-163-20535-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1974
CONSERVATION DIVISION
Wichita, Kansas

7-16-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wagner of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Wagner guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: 209 E. William, 700 Sutton Bldg., Wichita, Ks.

Lease Name: Mosher Well No. 5

Location: NE SE SE Sec 21 Twp. 8 Rge. (E)(W) 18

County: Rooks Total Depth 3465' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Wagner was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 675' and displace
70 sk cmt thru drill pipe. Heavy mud to 245' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Red V. Wagner
Conservation Division Agent