



15-163-20318-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1970
CONSERVATION DIVISION
Wichita, Kansas
8-5-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Abercrombie Drlg. has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg.

Complete Address: 801 Union Center Wichita, Ks.

Lease Name: Kramer Well No. 1

Location: NE SE SE Sec. 27 Twp. 8 Rge. (E)(W) 18

County: Rooks Total Depth 3249 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weber was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 700' and displace
50 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 50 sk cmt to base of cellar.

Very truly yours,

Geo F. Massey
Conservation Division Agent