

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15/03 20533-00-00

API NUMBER _____

LEASE NAME Dechant

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1
300' FWL 500' FSL NE
SPOT LOCATION _____

SEC. 26 TWP. 8 RGE. 18 (E) or (W) (W)

COUNTY Rooks

LEASE OPERATOR Murfin Drilling Company

Date Well Completed _____

ADDRESS 250 N. Water Suite 300 Wichita, Ks. 67202

Plugging Commenced 7-8-86

PHONE # (316)267-3241 OPERATORS LICENSE NO. _____

Plugging Completed 7-11-86

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3726'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10-3/4"	156'	none
				7"	3585'	478'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom was cemented from 2900' to 3726'. Shot Casing @2000', 1500', 991', 800', 478' and pulled a total of 16 joints of 7" casing. Plugged surface with 4 sacks hulls and 400 sacks econolite.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That JUL 29 1986 I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 28th day of July, 19 86



Irene Hoover
Notary Public

My Commission expires: _____

WELL LOG

18-143-20533-0000

COMPANY Murfin Drilling Company

SEC. 26 T. 8S R. 18W

FARM Dechant

NO. 1

LOC. SW SW NE

RID. NO. 15


TOTAL DEPTH 3726'

COUNTY

Rooks
KANSAS

COMM. 8-21-74

COMP. 8-30-74



CONTRACTOR Murfin Drilling Company

CASING

20 10 3/4" @ 156' w/135 sx
15 8
12 6 7" @ 3585' w/235 sx
13 5

ELEVATION 1968 GL 1973 KB

PRODUCTION SWD & Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

60 Surface soil - sand
135 Shale - sand
156 Shale
1245 Cement & shale & sand
1308 Red bed - shale
1343 Anhydrite
2550 Shale
3005 Shale & lime
3425 Lime
3480 Lime sand
3726 Lime
3726 TD

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1985

CONSERVATION DIVISION
Wichita, Kansas

6-23-86

State of Kansas

County of Sedgwick

ss:

I, James R. Daniels of the Murfin Drilling Company

upon this date that the above and foregoing is a true and correct copy of the log of the Dechant #1 well.



[Handwritten signature]