

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 4 TWP. 8 RGE. 21 E/W
Location as in quarters or footage from lines:
SW SE SW

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate Well
correctly on above
Section Platt.

Lease Owner Colorado Crude Exploration, Inc.
Lease Name Alexander Well No. 1
Office Address 12395 W. 53rd, Suite 102, Arvada, CO 80002
Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole
Date Well Completed 8-6-82
Application for plugging filed _____
Plugging commenced _____
Plugging completed 8-6-82
Reason for abandonment of well or producing formation Dry hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel
Producing formation _____ Depth to top _____ bottom _____ T.D. 3650'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 247' | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Mud laden fluid @ 3650' - 850'
80 sks cement @ 850'
40 sks cement @ 260'
10 sks cement @ 40'
10 sks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1982
AUG 12 1982

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Emphasis Oil Operations


STATE OF KANSAS COUNTY OF RUSSELL, ss.
Joe K. Branum (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
P.O. Box 506, Russell, KS 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 82.

My Commission expires: April 29, 1984.

Joyce Ann Ridgley
Notary Public.



EMPHASIS OIL OPERATIONS
P. O. Box 506
Russell, Kansas 67665

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1982
AUG 12 1982
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

OPERATOR: Colorado Crude Exploration, Inc.
12395 W. 53rd, Suite 102
Arvada, CO 80002

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Alexander WELL: #1

LOCATION: SW SE SW
Section 4-8-21W
Graham County, Kansas

Total Depth: 3650'

Elevation: 2085' K.B.

Commenced: 7-28-82

Completed: 8-6-82

Casing: 8-5/8" @ 247' with 160 sks cement

Status: Dry hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

| | | | |
|-----------------|-------|-----------------|-------|
| Top soil & sand | 40' | Shale & lime | 1647' |
| Sand & shale | 247' | Anhydrite | 1691' |
| Shale | 1160' | Lime & shale | 3460' |
| Sand | 1376' | Lime (RTD, LTD) | 3650' |


STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum
Joe K. Branum

Subscribed and sworn to before me this 7th day of August, 1982.

My Commission Expires: April 29, 1984.



Joyce Ann Ridgley
Notary Public