


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-163-02534-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Books _____ County. Sec. 34 Twp. 8S Rge. (E) 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$, NE $\frac{1}{4}$, NE $\frac{1}{4}$
Lease Owner Musgrove Petroleum Corp. & N.C.R.A.
Lease Name Veverka Well No. 1
Office Address 407 K.F.H. Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 22 19 51
Application for plugging filed May 22 19 51
Application for plugging approved May 22 19 51
Plugging commenced May 22 19 51
Plugging completed May 22 19 51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3509 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	209'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 200'.
Set plug at 200', spotted 15 sacks of cement.
Set second plug at 30' and filled with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corporation
Address 407 K.F.H. Building
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
407 K.F.H. Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 51

My commission expires December 5, 1951

Notary Public
STATE CORPORATION COMMISSION

28-3278-s 4-50-10M

PLUGGING
FILE SEC 34 T 8 R (9)
BOOK PAGE 84 LINE 7

JUN - 2 1951
6/2/51
CONSERVATION DIVISION
Wichita, Kansas

15-163-02534-00-00

CONTRACTOR'S WELL LOG

COMPANY: National Cooperative Refinery Association
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Veverka No. 1
 LOCATION: SE/4 NE/4 NE/4, Sec. 34-T8S-R19W
 Rooks County, Kansas
 COMMENCED: May 11, 1951
 COMPLETED: May 22, 1951

0	5	Cellar
5	50	Rock and clay
50	100	Blue shale and shells
100	680	Shale and shells
680	715	Red bed
715	980	Shale and shells
980	1120	Sand
1120	1180	Sandy red rock
1180	1380	Sandy shale
1380	1535	Shale and lime
1535	1740	Shale and shells
1740	1820	Shale and lime shells
1820	3218	Lime and shale
3218	3380	Lime
3380	3509	Lime and shale
	3509	Rotary Total Depth

Set 209' of 8-5/8" surface casing, cemented with 160 sacks.

Dry and Abandoned.

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Veverka #1, Sec. 34-8S-19W, Rooks County, Kansas, as reflected by files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By: Gordon L. Koelling
 Secretary

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 25th day of May, 1951.

Nadine J. Jirrel
 Notary Public

My commission expires: 12/5/51

PLUGGING
 FILE SEC 34 T 8 R 19 W
 BOOK PAGE 84 LINE 7

LIVED 6/2/51
 NOTARY COMMISSION
 JUN - 2 1951
 CONSERVATION DIVISION
 Wichita, Kansas