

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00365-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 71-56

LOCATION SE SE NE

SEC. 12 TWP. 8 RGE. 19

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Hance

Operator Deep Rock Oil Address Hutchinson, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3498 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 218' circulated with cement - 5 1/2" at 3457' cemented  
with 100 sax -

Filled with chat to 3440', set 4 sax cement with dump bailer,  
pulled 2980' 5 1/2", filled hole with mud to 215' set rock bridge  
and 20 sax cement, filled with mud to 35', set rock bridge and  
10 sax cement to bottom cellar.

RECEIVED

STATE CORPORATION COMMISSION

MAY 4 - 1951

5-4-51

CONSERVATION DIVISION  
Wichita, Kansas

Edouard J. ...  
District Conservation Agent

Date 5-2-51

PLUGGING

FILE SEC 12 T 8 R 19  
BOOK PAGE 71 LINE 36