

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20375-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 21 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
6-21-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Real Petroleum Company,

Complete Address 6810 West Kellogg, Wichita, Kansas.

Lease Name Harry Hance Well No. 1-V

Location NE-NW-SW Sec. 13 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3480'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.     

Operation Completed: Hour 9:30 AM Day 15 Month 6 Year 1971

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 425'.

Circulated hole with heavy mud. Pulled DP to 600' and displaced 70 Sx. cement thru  
DP from 600' to 375'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 6/22/71  
INV. NO. 3898-W