

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-163-20432-00-00

RECEIVED 4-27-72  
STATE CORPORATION COMMISSION  
APR 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Black Petroleum, Inc.

Complete Address 445 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Hance Well No. 1

Location NW SE SE Sec. 14 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3431'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Shields Drlg.

Address Russell, Kansas License No.       

Operation Completed: Hour 8:30 A Day 25 Month 4 Year 1972

The above well was plugged as follows:

RTD 3431' 8 5/8 csg set at 224' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Bo Z. Mandy  
Well Plugging Supervisor

INVOICED

DATE 5-3-72  
INV. NO. 5659-11