

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20124-0000

2-10-69  
RECEIVED  
STATE CORPORATION COMMISSION  
FEB 10 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Western Oil Fields Service

Complete Address: Box 163 Great Bend, Kansas

Lease Name Hance "A" Well No. 1

Location NE NE SE Sec. 14 Twp. 8 Rge. 19 (E) (W) X

County Rooks Total Depth 3464

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 12:15 P Day 8 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 3464' 8 5/8 csg set at 207' cwc 150 sk.

4 1/2 csg set at 3463' cw 150 sk cmt.

4 1/2 csg perf. (3112-3116)

Set plug at 3000' poured 10' sd (2990-3000) Dumped 4 sk cmt W/dump bailer. (2950-2990)

Shotoff and recov. 2695' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 16 sk gel W/4 sk hulls, 120 sk 50-50 pox cmt 6%,

4 sk gel, plug and 10 sk cmt W/1 sk hulls.

Cmt. (0-40) gel (40-200) cmt (200-700) gel (700-TD)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 2/10/69  
INV. NO. 9307-W