

15-163-20280-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Abercrombie Drilling Co., Inc.
Complete Address 801 Union Center Wichita, Kansas
Lease Name Veverka "B" Well No. 1
Location C E/2 NE SE Sec. 20 Twp. 8 Rge. (E) (W) 19
County Rooks Total Depth 3485
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 2:30A Day 22 Month 12 Year 1969

The above well was plugged as follows:

RTD 3485' of 6 1/2" hole. 8 5/8 csg set at 255' cwc 155 sk-Cmt. Mat 50-50 poz 6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sk cmt
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED
DATE 12-29-69
INV. NO. 1164-W