

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-00820-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1963

CONSERVATION DIVISION
Wichita, Kansas

12/17/63

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kaiser - Francis

Complete Address: 905 Palace Bldg Tulsa, Okla

Lease Name Bray Est Well No. 1

Location SE SW SW Sec. 20 Twp. 8 Rge. (E) (W) 19

County Rooks Total Depth 3466

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 10AM Day 12 Month 12 Year 63

The Above well was plugged as follows:

8 5/8" 258' circulated with cement - 5 1/2" 3462' with 125 sax cement
sand back to 3450', set 4 sax cement with dump bailer - pulled 2650'
5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550' - (25
sax Gel) - displaced 20 sax cement through 5 1/2" at 550', heavy mud to 200
displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set
bridge and filled to bottom cellar with cement.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Perry
Well Plugging Supervisor

DATE 12/18/63
INV. NO. 8310-W