

15-163-20123-00-00

Form CP-3
Rev. 6-26-62

KANSAS

af

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9/6/68

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address: 801 Union Center Wichita, Kansas

Lease Name Veverka Well No. 1

Location SE SE NE Sec. 20 Twp. 8 Rge. 19 (E) (W) X

County Rooks Total Depth 3485

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 7 P Day 4 Month 9 Year 1968

The Above well was plugged as follows:

RTD 6 3/4 hole to 3485' 7 5/8 csg set at 238' cwc 125 sc. 75 sx poz cem. W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 50 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 17 sx cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/4 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED
DATE 9/6/68
INV. NO. 8413-W