


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 35 Twp. 8S Rge. 18 (E) 18 (W)
Location as "NE/CNW&SW&" or footage from lines NE SE SE
Lease Owner Chief Drilling Co., Inc.
Lease Name Russ Well No. 1
Office Address Box 797 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/22 19 63
Application for plugging filed 9/22 19 63
Application for plugging approved 9/22 19 63
Plugging commenced 9/22 19 63
Plugging completed 9/22 19 63
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3534 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	205	8-5/8"	205	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 550'
Mixed 20 sacks cement through drill pipe
1/3 sack hulls and wooden plug set @ 180'
Mixed 20 sacks cement through drill pipe
1/3 sack hulls and wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1963
SEP 25, 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CHIEF DRILLING CO., INC.

(Signature) V. Richard Hoover
Box 797 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 63

My commission expires Jan. 26, 1967.
Carmen R. Cook
Notary Public.

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

RUSS #1
NE SE SE Sec. 35-8S-18W
Rooks County, Kansas

Whitestone Petroleum Corp.
900 Vaughan Building
Dallas, Texas

Commenced: 9-13-63
Completed: 9-22-63

Dry & Abandoned

Contractor: Chief Drilling Co., Inc.

Casing Record: 8-5/8" set @ 205' w/135 sacks Sunset Cement.

RECEIVED
STATE CORPORATION COMMISS.

SEP 25 1963

SEP 25 1963
CONSERVATION DIVISION
Wichita, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale & Rock	0	204
Shale & Sand	204	1385
Anhydrite	1385	1430
Shale & Shells	1430	1985
Lime & Shale	1985	2635
Lime	2635	2745
Lime & Shale	2745	2950
Lime	2950	3172
Lime & Shale	3172	3215
Lime	3215	3436
Lime & Shale	3436	3464
Dolomite	3464	3534
Total Depth	3534	

ELEVATION
2037 Gr.
2039 D.F.
2042 K.B.

FORMATION TOPS

Anhydrite	1835 + 657	
Topeka	2955 - 913	2956 - 914
Heebner	3172 - 1130	3171 - 1129
Toronto	3194 - 1152	3195 - 1153
Lansing	3215 - 1173	3214 - 1172
Base Kansas City	3436 - 1394	3437 - 1395
Arbuckle	3464 - 1422	3463 - 1421
Total Depth	3534 - 1492	

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE SE SE Sec. 35-8S-18W, Rooks County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 23rd day of September, 1963.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.