

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-21,189-00-0

LEASE NAME Harris

WELL NUMBER 5

4950 Ft. from (S) Section Line

4950 Ft. from (E) Section Line

SEC. 34 TWP. 8 RGE. 18 (X) or (W)

COUNTY Rooks

Date Well Completed 01-28-81

Plugging Commenced 09-29-94

Plugging Completed 09-29-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Gene Brown Company

ADDRESS P O drawer 220 Plainville, Ks 67663

PHONE# (913) 434-4811 OPERATORS LICENSE NO. 5635

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-28-94 (date)

by Dennis Hamel - Verbal (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation L.K.C. Depth to Top 3110 Bottom 3356 T.D. 3410

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	169	8 5/8	169	None
Production		0	3425	4 1/2	3424	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Perf casing at 2000 - 1350 - 750. Pumped 30 sks cement with 100# hulls down 8 5/8 to 300 psi. Pumped 220 sks cement with 400# hulls down 4 1/2 to 400 psi. Shut in at 100 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. UnApp

Address Russell, Ks

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss.

Thomas M. Brown (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Thomas M Brown

(Address) 701 S. W. 9th Plainville Ks.

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 94

Bonita K. Shubert
 Notary Public

My Commission Expires: July 2, 1997

