

15-163-00243-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rocks \_\_\_\_\_ County. Sec. 35 Twp. 8 Rge. (E) 18 (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines \_\_\_\_\_ NW NW NW  
Lease Owner. Westgate-Greenland Oil Company  
Lease Name. Radke Well No. 1  
Office Address. 1022 Union National Bank Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed. December 31, 1948 19\_\_\_\_  
Application for plugging filed. December 31, 1949 orally 19\_\_\_\_  
Application for plugging approved. January 10, 1949-written 19\_\_\_\_  
Plugging commenced. January 1, 1949 19\_\_\_\_  
Plugging completed. January 1, 1949 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>surface</u>		<u>0</u>	<u>158.7</u>	<u>8 5/8"</u>	<u>158.7</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud from total depth to 160 feet  
Set plug at 160 feet and dumped 15 sacks cement  
Filled with heavy mud from 160 feet to 30 feet  
Dumped 10 sacks cement filling to cellar base

JAN 18, 1949

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. E. Bitler  
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

G. E. Bitler (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

G. E. Bitler

1022 Union National Bank Bldg, Wichita 2, Ks  
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of January, 1949

Esther Russell

My commission expires May 25, 1949

Notary Public.

PLUGGING  
FILE SEC 35 T 8 R 18 W  
BOOK PAGE 79 LINE 3

COMPANY: Westgate Greenland Oil Company  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: Radke #1  
 LOCATION: NW NW NW Section 35-8-18W  
 Rooks County, Kansas  
 ELEVATION: 2029  
 COMMENCED: December 17, 1948  
 COMPLETED: December 31, 1948

0	to	170	Yellow Clay & shale
170	to	520	Shale & shells
520	to	905	Shale
905	to	1120	Sand
1120	to	1300	Red bed
1300	to	1410	Red bed & shale
1410	to	1455	Anhydrite
1455	to	1800	Shale & shells
1800	to	1840	Iron & shale
1840	to	2090	Shale & shells
2090	to	2270	Lime & shale
2270	to	2315	Lime
2315	to	2615	Lime & shale
2615	to	2680	Lime
2680	to	2970	Lime & shale
2970	to	3110	Lime
3110	to	3135	Shale
3135	to	3205	Lime & shale
3205	to	3374	Lime
3374	to	3430	Shale & lime
3430	to	3468	Lime
3468	to	3478	Arbuckle
3478	to	3530	Lime
		3530	T. D.

RECEIVED

JAN 18 1949

8 5/8" casing set at 158 feet - Cemented with 90 sacks cement

Top arbuckle 3461

Dry & abandoned - Measurements taken from top of derrick floor

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Radke #1, Section 35-8-18W, Rooks County, Kansas, as reflected by files of the Jackson Drilling Corporation.

*Clare A. Stewart*  
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 17th day of January 1949.

*Dorothy J. Wilson*  
 Dorothy J. Wilson

My Commission expires November 30, 1950

FILE NO. 35-8-18W  
 PAGE 79 OF 3