


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-163-00361-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 6 Twp. 8 Rge. _____ (E) 19 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW SE
Lease Owner The Carl Todd Drilling Company, et al
Lease Name McCormick Well No. 1
Office Address 404 KFH Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed November 21, 19 51
Application for plugging filed November 23 19 51
Application for plugging approved November 20 19 51
Plugging commenced November 20 19 51
Plugging completed November 21 19 51
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, by telephone.

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	1120	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 250'. Bridged hole with wooden plug at 250, 1/2 sack hulls, 15 sacks cement. Filled with heavy mud to 40', bridged with wooden plug, 1/2 sack hulls, 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Carl Todd Drilling Company
Address 404 KFH Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Carl Todd (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Carl Todd

404 KFH Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1951

My commission expires May 17, 1954.

28-5091-s 8-50-10M



Notary Public. Martha Loapp

NOV 2 1951

11-24-51

WELL LOG

15-163-00361-00-00

COMPANY: Carl Todd Drilling Co.
 LEASE: Mc Cormick #1.

NW-NW-SE, Sec. 6,
 Twp. 8, Rge. 19W,
 Rooks County, Kansas.

ELEVATION: 1885 R.B. 1883 DF
 NOTE: All meas Rotary Pushing.

0	150 Sand & shale
150	400 Shale & shells
400	445 Shale & shells
445	625 Sand
625	745 Shale & shells
745	840 Shale & Redbed
840	975 Sand
975	1060 Sand & shale
1060	1100 Shale
1100	1110 Shale & shells
1110	1120 Redbed
1120	1345 Redbed & shale
1345	1380 Anhydrite
1380	1605 Shale & shells
1605	1785 Shale & shells
1785	1940 Shale & shells
1940	2035 Shale & shells
2035	2190 Shale & shells
2190	2325 Shale & lime
2325	2435 Lime & shale
2435	2505 Lime & shale
2505	2685 Lime & shale
2685	2870 Shale & lime
2870	2970 Shale & Lime
2970	3005 Lime & shale
3005	3060 Lime & shale
3060	3110 Shale & lime
3110	3170 Shale & lime
3170	3190 Lime
3190	3217 Lime
3217	3283 Lime
3283	3350 Lime
3350	3358 Lime & shale
3358	3415 Lime
3415	T.D. (R.B. Meas.)

COMMENCED: 11-9-51
 COMPLETED: 11-21-51

CASING RECORD:

8 5/8" Surface casing set at
 1120 Ft. w/525 sks (275-2% Gel, 250
 reg. cement & 3 sks CC. Cemented
 by Halliburton.

D.S.T.

3190', Tool open 30 min. Recovered
 180 ft. muddy salt water. Good Blow.
 B.H. P. 15 min. 1200#.

Ran Schlumberger log to Total Depth.

TOPS:

Anhydrite.	1345	No Conglomerate	
Heebner	3064 (-1179)	Arbuckle	3358 (-1473)
Lansing	3102 (-1217)	Total Depth	3415 (-1530)
Base K.C.	3313 (-1428)		

STATE OF KANSAS) SS
 COUNTY OF ELLIS)

I hereby confirm that the above and foregoing is a true and correct copy of the log of the Mc Cormick #1, located NW-NW-SE, Sec. 6, Twp. 8, Rge. 19W, Rooks County, Kansas.

CONTRACTOR: STRAIN DRILLING CO.

BY P.C. Strain
 P.C. Strain

Subscribed and sworn to me before this 24, day of November, 1951
 My Commission expires July, 18, 1955.

Robert Ann Laine
 NOTARY PUBLIC.

6 2 9W
 D.C. 23

11-26-51