



15-163-20375-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas
6-21-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. T. F. Brown of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Real Petroleum Company,

Complete Address: 6810 West Kellogg, Wichita, Kansas.

Lease Name: Harry Hance Well No. L-V

Location: NE-NW-SW Sec. 13 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3480' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brown was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 425'.

Circulate hole with heavy mud. Pull DP to 600' and displace 700-Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent