

State of Kansas



15-163-20636-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1976  
CONSERVATION DIVISION  
Wichita, Kansas  
9-17-76

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B&B Drlg. has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil, Inc.

Complete Address: 1625 Vickers KSB&T Bldg., Wichita, Ks.

Lease Name: Boyd-Cunningham Well No. 1

Location: C SE SW NW Sec. 15 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3200' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 660' thru drill

pipe. "eavy mud to 185' set 20 sk cmt plug thru drill pipe. "eavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Ruo Wassup  
Conservation Division Agent