

15-163-20051-00-00

FORM - CP-2
Rev. 9-8-64

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
AUG 28 1967
AUG 28 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Harre of Thoroughbred Drlg. has this

date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Co.,

Complete Address: Fourth Floor, Petroleum Bldg. Tulsa, Okla.

Lease Name: Clell Stice Well No. 1

Location: SE NE NW Sec. 21 Twp. 8 Rge. 19 (E)(W) X

County Rooks Total Depth 3518 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Harre was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
100 sc cement thru drill pipe. Heavy mud to 180' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

Geo. F. Massey
Conservation Division Agent