

State of Kansas



15-163-20120-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 28 1968
 CONSERVATION DIVISION
 Wichita, Kansas

8/28/68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Prospect Oil, Inc.

Complete Address: 811 Union Center Wichita, Kansas

Lease Name: Lowry Well No. 1

Location: NW SW SW Sec. 20 Twp. 8 Rge. 19 (E)(W) X

County: Rooks Total Depth 3445' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 715' and displace

100 cu. Ft. of cement thru drill pipe. Heavy mud to 245' set cementing

plug and displace 20 cu. Ft. of cement thru drill pipe. Heavy mud to

40' set cementing plug, 1/2 sc hulls and 10 cu. ft. of cement to base

of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo F. Massey
 Conservation Division Agent