



15-163-20280-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12/29/69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Abercrombie Drlg. Inc. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drlg., Inc.

Complete Address: 801 Union Center Wichita, Ks.

Lease Name: Veverka "B" Well No. 1

Location: C E/2 NE SE Sec. 20 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3485 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Cook was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo P. Messing  
Conservation Division Agent