



15163-19145-00-00

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS
JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION

JAN 8 1963
15-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date Jan 1 - 1963, 1963, authorized the following plugging operation:

Operator's full Name: Morris G. Vewerka

Complete Address: Plainville Kansas

Lease Name: C. L. Hame "O" Well No. 1

Location: C. Se. 1/4 Sec. 24 Twp. 8 Rge. 19 (E)(W)

County: Rooks Total Depth: 3550

Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐

D & A ☒ Other well as hereafter indicated: Rotary dry hole

Operator was instructed to plug well as follows:

Jet pits circulate hole with heavy mud, set
cementing plug at 550' and displace 20 sac cement
thru drill pipe, heavy mud to 180' set cementing plug
and displace 20 sac cement, heavy mud to 40' set
plug, dump 1/2 sac hulls and 10 sac cement,

Very truly yours,

Gilbert P. Leiker

