



15-163-20477-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1972

CONSERVATION DIVISION
Wichita, Kansas

12/26/72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of C & G Drlg. has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie & Maderia Oil

Complete Address: 412 Union Center Wichita, Kansas

Lease Name: Kellogg Well No. 1

Location: SW SE SE Sec. 22 Twp. 8 Rge. (E)(W) 19

County: Rooks Total Depth 3402' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Boyd Massey
Conservation Division Agent