

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 22 1972
MAY 22 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pate - Dombaugh & Martin Explorations

Complete Address 502 Union Center Wichita, Kansas

Lease Name Harris Well No. 1

Location SE NE NE Sec. 34 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3480'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling Oil

Address Victoria, Kansas License No.

Operation Completed: Hour 9 A Day 18 Month 5 Year 1972

The above well was plugged as follows:

RTD 3480' 8 5/8 csg set at 197' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 190' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo A. Murray*
Well Plugging Supervisor

INVOICED
DATE 5/25/72
INV. NO. 5742-W