

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1973
JAN 2 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pate-Dombaugh & Martin Exploration
Complete Address 502 Union Center, Wichita, Kansas
Lease Name Peace Well No. 1
Location SW SE SW Sec. 34 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3433'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Dreiling Oil
Address Victoria, Kansas License No.
Operation Completed: Hour 4:45 P Day 30 Month 12 Year 1972

The above well was plugged as follows:

RTD 3433' 8 5/8 csg set at 206' cwc 150 sx. Cmt. Mat. 50-50 poz cmt W/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sx
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Reo J. Massey
Well Plugging Supervisor

INVOICED

DATE 1/3/73
INV. NO. 6804-u