

15-163-20486-00-00

Form CP-3
Rev. 6-4-68

J
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1973
APR 19 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.
Complete Address Route # 2 Victoria, Kansas
Lease Name Peace Well No. 2
Location NE SE SW Sec. 34 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3458'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 11 A M Day 17 Month 4 Year 1973

The above well was plugged as follows:

RTD 3458' 8 5/8 csg set at 206' cwc 135 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 640' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 4/19/73
INV. NO. 7261-W