

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,700 -00-00 (of this well)

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1977
MAY 27 1977
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Co.
Complete Address 617 Union Center, Wichita, Kansas
Lease Name Peace Well No. 1
Location 100' So. of NE NE SE Sec. 34 Twp. 8 Rge. (E) (W) 18
County Rooks Total Depth 3530'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 4:15 P Day 24 Month 5 Year 1977

The above well was plugged as follows:

RTD 3530' 8 5/8 csg set 177' cwc 160 sk. Flg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.
Heavy mud to 175' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED
DATE 5-27-77
INV. NO. 5238-W