



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

MAY 13 1974  
May 13, 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum, Inc.  
Complete Address R. R. # 2 Great Bend, Kansas 67530  
Lease Name Carmichael LKC Unit Well No. TR 1 W 1  
Location NE NW SW Sec. 33 Twp. 8 Rge. (E) (W) 18  
County Rooks Total Depth 3432'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated       

Plugging Contractor Pipe Pullers, Inc.  
Ellinwood, Ks.  
Address Box 486, Ellinwood, Kansas 67526 License No. 462  
Operation Completed: Hour 11 A Day 8 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 3432' 8 5/8 csg set at 2001' cwc 125 sk.  
5 1/2 csg set at 3431' cw 125 sk.  
5 1/2 csg PBTB 3303" with perf. (3150-3160)  
Set 5 1/2 wood plug at 3000' -poured 20' sd -dumped 4 sk cmt W/dump bailer. (2950-3000)  
Cutoff and recovered 631' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 15 sk gel & water W/3000 lbs hulls - 50 sk cmt -10 sk  
gel & water -released 8 5/8 plug and pumped 50 sk cmt by Allied Cementing Co. PP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 5/14/74  
INV. NO. 9100-W