

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1974  
MAY 13 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum, Inc.  
Complete Address R. R. # 2 Great Bend, Kansas 67530  
Lease Name Carmichael L KC Unit Well No. Tr 1 W 2  
Location SE NW SW Sec. 33 Twp. 8 Rge. (E) (W) 18  
County Rooks Total Depth 3468'  
Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated     

Plugging Contractor Pipe Pullers, Inc.  
Address Box 486 Ellinwood, Kansas 67526 License No. 462  
Operation Completed: Hour 12:30 P Day 8 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 3468' 8 5/8 csg set at 201' cwc 135 sk.  
5 1/2 csg set at 3466' cw 75 sk cmt.  
5 1/2 csg PBD 3293' & perf. (3090-3095)  
Set 5 1/2 wood plug at 3000' -poured 20' sd -dumped 4 sk cmt W/dump bailer. (2950-3000)  
Cutoff & recovered 600' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs hulls -50 sk cmt -10 sk gel  
& water -released 8 5/8 plyg and pumped 50 sk cmt by Allied Cementing C. PP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 5/14/74  
INV. NO. 9101-U