

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1977
OCT 17 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20, 744 00-00 (of this well)

Operator's Full Name Two-Way Oil Co.

Complete Address 1000 Southwest 2nd, Plainville, Kansas

Lease Name Harris Well No. 1

Location C SW NW Sec. 34 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3405'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Helberg Drlg.

Address Morland, Kansas License No.

Operation Completed: Hour 10:45 A Day 16 Month 10 Year 1977

The above well was plugged as follows:

RTD 3405' 8 5/8 csg set 164' cwc 150 sk. Flg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.
Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10-17-77
6035.0

Signed: Leo Massey
Well Plugging Supervisor