

KANSAS

Form CP-3

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION
RECEIVED
MAY 11 1978
MAY 11 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 - 20723-00-00 (of this well)

Operator's Full Name Two-Way Oil Co.

Complete Address 1000 SW 2nd., Plainville, Kansas 67663

Lease Name Dechant Well No. 4

Location C W/2 SW NE Sec. 35 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3445'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. tools by Brown Bros. Well Service

Address Plainville, Kansas License No. _____

Operation Completed: Hour 4:30 P Day 9 Month 5 Year 1978

The above well was plugged as follows:

Total Depth 3445' 8.5/8 csg set 170' cwc 140 sk.

4 1/2 csg set 3444' cemented W/150 sk.

4 1/2 csg Perf. (3192')

Filled 4 1/2 csg W/sd (3445'-3080') dumped 3 sk cem. W/dump bailer. (3080'03050')

Cutoff & recovered 2670' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs

hulls -followed with 70 sk 50-50 poz 6% -displaced with 5 sk gel & water and

capped with cementing plug & 60 sk 50-50 poz 6% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-11-78

INV. NO. 7290-4

Signed: [Signature]
Well Plugging Supervisor