

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1977
NOV 14 1977
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163- 20,751 (Cons this well)

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address 801 Union Center, Wichita, Kansas

Lease Name Radke "B" Well No. 2

Location C SE NE NW Sec. 35 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3460'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4:30 A Day 9 Month 11 Year 1977

The above well was plugged as follows:

RTD 3460' 8 5/8 csg set 206' cwc 150 sx. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-14-77

INV. NO. 6192-W

Signed: [Signature]
Well Plugging Supervisor